



ENLARGED UTILITY ROOM
SCALE: 1/4" = 1'-0"

SYMBOL	MANUFACTURER NAME	CATALOG NO.	FIXTURE WATTS	LAMP TYPE	MOUNTING	REMARKS
F-1	DAY-BRITE LITHONIA METALLUX	NA242-120 2LB-240X-120 CC-440A-120R00	100	2-F40W	SURFACE	NOTE 6
F-3	WLRCD PRESCLUTE	J-SI-T100 400-HF-1-DL	100	A-19,IF	RECESSED	DAMP LOCATION
F-11	WANNING PRESCLUTE	CP1-200S-LS 56T-C	450 300	3-SEWING 3-100W INC.	PENDANT	NOTE 1 & 6
F-20	WLRCD PRESCLUTE	B12 CFX-10	100	A-19,IF	SURFACE	
F-30	PRESCLUTE	S120CG/S100GLL	150	RAOFL	FLUSH WITH GRADE	ON LOCATION LABEL
F-31	PRESCLUTE	5322	150	RAOFL	1/2" NIPPLE, 1/2" CAST JUNCTION BOX	NOTE 2
F-32	WANNING VISA	LP1-091-10A 9804-CV1 NOTE 4	NOTE 3	A-19,IF	PENDANT	NOTE 5 & 7
F-33	WANNING VISA	LP1-090-10 9804-CV1 NOTE 4	100	A-19,IF	PENDANT	NOTE 5 & 7
⊙	DAY-BRITE DUAL-LITE	B-311G W/BST1 S0WB OR G0WB	25	INCLUDED	WALL	NOTE 6
⊙	DAY-BRITE DUAL-LITE	B-311G W0WB	25	INCLUDED	SURFACE	NOTE 6

- NOTES: FIXTURE SCHEDULE
- PROVIDE WITH SWIVEL BRACKET AND MOUNT BOTTOM OF FIXTURE OR GLOBE (10" OR 9 1/2" O.D. GLOBE) 9'-0" A.F.F. PROVIDE SUFFICIENT MOUNTING HARDWARE AND SUPPORT FOR FIXTURE AT MOUNTING LOCATION. ALSO FINISHED SHALL BE BRUSHED ALUMINUM.
 - WEATHERPROOF CAST J.B.'S SHALL BE SAWN-RECESSED IN 12" SQ. X 12" H. CONC. BASE. BASE SHALL BE (TOP) 2" ABOVE GRADE. SEE ARCH. SHEET C-1 FOR EXACT LOCATION OF BLDG. IDENTIFICATION SIGN, MOUNT 2 FIXTURES 2'-0" APART AND ON EITHER SIDE OF E. DIRECT FIXTURES AT SIGN PER ARCH. DIRECTIONS.
 - ON LOW CEILING FIXTURE PROVIDE 100WATT LAMP AND ON HIGH CEILING PROVIDE 1-200WATT LAMP, AS INDICATED ON DRAWINGS. NOTE DO NOT EXCEED MAX. WATTAGE FOR EXIST. FIXTURE BEING REMOVED.
 - PROVIDE EXPANDED METAL GRILLE IN BOTTOM.
 - PROVIDE NEW OUTLET BOX FLUSH W/CEILING. COORDINATE BOX LOCATION WITH NEW CEILING CONSTRUCTION IN THAT AREA. AFTER REMOVAL OF OLD FIXTURE, CONNECT FIXTURE TO EXISTING CIRCUIT, AS REQUIRED.
 - SOME FIXTURE ARE TO BE CONNECTED TO EXISTING CIRCUIT AND REFER TO SHEET E-1 FOR THOSE LOCATIONS.
 - PROVIDE FIXTURES AT LOW CEILING W/ G' STEM AND MOUNT FIXTURES AT HIGH CEILING TO MATCHING HEIGHT.

ELECTRICAL NEW WORK FLOOR PLAN
SCALE: 1/8" = 1'-0"

DILLS · AINSCOUGH & ASSOCIATES
 ARCHITECTS · PLANNERS · INTERIOR DESIGNERS
 1932 N. Greenheck Road, Suite 103, Virginia Beach, VA 23464 · (804) 461-1252

PORTSMOUTH WARD
 ADDITION / REMODELING
 NEWPORT NEWS, VIRGINIA STATE
 PORTSMOUTH, VIRGINIA

395931

THE CHURCH OF JESUS CHRIST
 OF LATTER-DAY SAINTS

Revisions
 Δ 12-5-83 APPENDIX #1
 Δ AS BUILTS 10-7-89

Designed TEW

Drawn GUN

Checked WNC

Scale AS SHOWN

Date

Project No.

Sheet No. 25

E-2

of 32 Sheets